



QUESTIONS & ANSWERS

RFQ: 22-015 – NORTH SPOOKY LANE ROADWAY IMPROVEMENTS

1. What is the location for erosion control? **Contractor to place reinforced silt fencing between disturbed areas and wetlands to prohibit sediment from entering wetlands. Add standard construction entrance at the south end of North Spooky to reduce sediment tracking onto SR 30A. Add inlet protection to new inlets after installation until final course of asphalt is applied.**
2. Is excavation included with clearing and grubbing? **Yes**
3. What is the project estimate? **Project was originally estimated at \$108,000 in January 2022. It is anticipated that industry costs have since increased. \$650,000 was budgeted for the project.**
4. MOT details were requested. **According to the plans, there are 11 driveways along North Spooky Lane and those residents need uninterrupted access to their homes. Contractor must maintain one lane of traffic at all times. MOT must be in accordance with the current edition of the FDOT standard plans.**

This Question and Answer now becomes a part of the original ITB. Acknowledge receipt of this Question and Answer and include this form with your submission. Failure to do so will result in your Bid being found non-responsive.

Bidder: _____ By: _____

Address: _____ Phone: _____

City, State: _____ Date: _____

Authorized Signature